



Avaya Solution & Interoperability Test Lab

Application Notes for configuring Ascom i62 with Avaya Aura® Communication Manager and Avaya Aura® Session Manager – Issue 1.0

Abstract

These Application Notes describe the configuration steps for provisioning Ascom's i62 VoWiFi handsets to interoperate with Avaya Aura® Communication Manager and Avaya Aura® Session Manager.

Readers should pay attention to **Section 2**, in particular the scope of testing as outlined in **Section 2.1** as well as any observations noted in **Section 2.2**, to ensure that their own use cases are adequately covered by this scope and results.

Information in these Application Notes has been obtained through DevConnect compliance testing and additional technical discussions. Testing was conducted via the DevConnect Program at the Avaya Solution and Interoperability Test Lab.

1. Introduction

These Application Notes describe the configuration steps for provisioning Ascom's i62 VoWiFi (i62) handsets to interoperate with Avaya Aura® Communication Manager R8.0.1 and Avaya Aura® Session Manager R8.0.1. Ascom's i62 handsets are configured to register with Session Manager and are configured with the 9620 SIP endpoint template. The Ascom i62 handsets then behave as third-party SIP extensions on Communication Manager. The handsets are able to make/receive internal and PSTN/external calls and have full voicemail and other telephony features available on Communication Manager.

2. General Test Approach and Test Results

The interoperability compliance testing evaluates the ability of Ascom i62 handsets to make and receive calls to and from Avaya H.323, Avaya SIP, and PSTN endpoints. Avaya Aura® Messaging was used to allow users leave voicemail messages and to demonstrate Message Waiting Indication and DTMF on the Ascom i62 handsets.

DevConnect Compliance Testing is conducted jointly by Avaya and DevConnect members. The jointly-defined test plan focuses on exercising APIs and/or standards-based interfaces pertinent to the interoperability of the tested products and their functionalities. DevConnect Compliance Testing is not intended to substitute full product performance or feature testing performed by DevConnect members, nor is it to be construed as an endorsement by Avaya of the suitability or completeness of a DevConnect member's solution.

Avaya recommends our customers implement Avaya solutions using appropriate security and encryption capabilities enabled by our products. The testing referenced in these DevConnect Application Notes included the enablement of supported encryption capabilities in the Avaya products. Readers should consult the appropriate Avaya product documentation for further information regarding security and encryption capabilities supported by those Avaya products.

Support for these security and encryption capabilities in any non-Avaya solution component is the responsibility of each individual vendor. Readers should consult the appropriate vendor-supplied product documentation for more information regarding those products.

For the testing associated with these Application Notes, the interface between Avaya systems and Ascom i62 VoWiFi handsets did not include use of any specific encryption features as requested by Ascom.

Avaya's formal testing and Declaration of Conformity is provided only on the headsets/Smartphones that carry the Avaya brand or logo. Avaya may conduct testing of non-Avaya headset/handset to determine interoperability with Avaya phones. However, Avaya does not conduct the testing of non-Avaya headsets/Smartphones for: Acoustic Pressure, Safety, Hearing Aid Compliance, EMC regulations, or any other tests to ensure conformity with safety, audio quality, long-term reliability or any regulation requirements. As a result, Avaya makes no representations whether a particular non-Avaya headset will work with Avaya's telephones or with a different generation of the same Avaya telephone.

Since there is no industry standard for handset interfaces, different manufacturers utilize different handset/headset interfaces with their telephones. Therefore, any claim made by a headset vendor that its product is compatible with Avaya telephones does not equate to a guarantee that the headset will provide adequate safety protection or audio quality

2.1. Interoperability Compliance Testing

The compliance testing included the test scenarios shown below. Note that when applicable, all tests were performed with Avaya SIP, Avaya H.323, Ascom i62 and PSTN endpoints.

- Basic Calls
- Session Refresh Timer
- Long Duration Call
- Hold, Retrieve and Brokering (Toggle)
- Feature Access Code dialing
- Attended and Blind Transfer
- Call Forwarding Unconditional, No Reply and Busy
- Call Waiting
- Call Park/Pickup
- EC500, where Avaya deskphone is the primary phone and i62 handset being the EC500 destination.
- Multi-Device Access (MDA)
- Attended Conference (also local three-way calling)
- Do Not Disturb
- Calling Line Name/Identification
- Codec Support (G.711, G.729, G.722)
- DTMF Support
- Voice Mail, Message Waiting Indication
- Serviceability

Note: Compliance testing does not include redundancy testing as standard. Where some LAN failures were simulated, and the results observed, there were no redundancy or failover tests performed.

2.2. Test Results

The tests were all functional in nature and performance testing and redundancy testing were not included. All test cases passed successfully with the following observations/limitations noted below:

1. An invalid password configured on the i62 invokes a “race condition” where the i62 attempts multiple registrations. Ascom MRS–293.
2. When using the EC500 (concurrent call) feature, if an i62 handset or an Avaya endpoint answers the call before two rings, the call is dropped. This is due to the “Cellular Voice Mail Detection” field default value seen in “off-pbx-telephone configuration-set” form of Communication Manager. The default value for this field is “timed (seconds): 4” which means that if Communication Manager receives an answer within 4 seconds then it will be considered as the cellular voicemail picking up the call, and so call will be dropped and proceed to do Communication Manager coverage processing instead. The workaround is to answer the call after 2 rings or change the “Cellular Voice Mail Detection” field value to “none” or decrease “timed” value. Note that changing the “off-pbx-telephone configuration-set” affects all users in the same set, so if cellular users are grouped with i62 handset users, calls may be answered by a cellular user’s voicemail instead of following the coverage criteria in Communication Manager.
3. When an i62 handset is configured as an EC500 destination for an Avaya endpoint, an incoming call to the Avaya endpoint will ring both the Avaya endpoint and the i62 handset. When the call is declined on the i62 handset, the Avaya endpoint continues to ring as per normal design.
4. All compliance testing was done using UDP and TCP (preferred) as the transport protocol.
5. Negotiation of G.722 between endpoints, such as the Ascom i62, requires support for the codec to be configured on Communication Manager.
6. When an Avaya endpoint or an i62 handset calls another i62 handset, after the called i62 handset declines the call, the display for the i62 calling party shows busy whereas the Avaya calling party receives the busy tone.
7. In the blind transfer scenario involving three i62 handsets, where A is the calling, B is the called and transfer-from and C is the transfer-to parties. The display on the transfer-to party C showed “Redirected x y” where “x” is the extension number of the calling party A and “y” is the name of the transfer-from party B. According to Ascom, transfer-to party C displayed information conveyed by Communication Manager, and “redirected” was displayed because the INVITE included a History-Info header (Ascom ticket: MRS-145).
8. Ascom i62 handset supports third party conference, which is, i62 makes two calls simultaneously and conferences the calls locally.
9. When multiple voice messages are left for an i62 handset, the handset shows the total number of messages as only “1” in the display even though there are multiple messages. This is because there is no counter information sent in the NOTIFY from Avaya Aura® Messaging.

10. For Multi-Device Access (MDA), the i62 needs to be configured using and registering through Endpoint ID. Also, the MWI configuration has to be identical on all i62 handsets that are configured for MDA. Refer to **Section 7.3** for details.
11. Per design, i62 handsets do not have a redial button. User needs to use “Call List” and redial the numbers.
12. When outgoing calls are configured to be restricted for an i62 handset on Communication Manager, the i62 display showed “No Channel Available” when user attempted to make an outbound call.

2.3. Support

Support from Avaya is available by visiting the website <http://support.avaya.com> and a list of product documentation can be found in **Section 10** of these Application Notes. Technical support for the Ascom i62 wireless handsets can be obtained through a local Ascom supplier or Ascom global technical support:

- Email: support@ascom.com
- Help desk: +46 31 559450

3. Reference Configuration

Figure 1 shows the network topology during compliance testing. The Ascom i62 VoWiFi handsets connect to an Ascom approved wireless router which is placed on the LAN. The i62 handsets register with Session Manager to be able to make/receive calls with the Avaya H.323, SIP and digital endpoints on Communication Manager and with the PSTN. The handsets are configured by Ascom Windows Portable Device Manager (WinPDM) using the Ascom Desktop Programmer DP1.




Figure 1: Network Solution of Ascom i62 with Avaya Aura® Communication Manager R8.0.1 and Avaya Aura® Session Manager R8.0.1

4. Equipment and Software Validated

The following equipment and software were used for the compliance test.

Avaya Equipment	Software / Firmware Version
Avaya Aura® System Manager running on a virtual server	System Manager 8.0.1.1 Build No. – 8.0.0.0.931077 Software Update Revision No: 8.0.11.039340 Service Pack 1
Avaya Aura® Session Manager running on a virtual server	Session Manager R8.0.1 Build No. – 8.0.1.1.801103
Avaya Aura® Communication Manager running on a virtual server	R8.0.1.1.0 – FP1SP1 R018x.00.0.822.0 Update ID 00.0.822.0-25183
Avaya Aura® Messaging running on a virtual server	7.0 SP0
Avaya Media Gateway G450	40.20.0 /2
Avaya Aura® Media Server	Appliance Version R8.0.0.6 Media Server 8.0.0.150 Element Manager 8.0.0.150
Avaya 96x1 H323 Deskphone	6.6604
Avaya 96x1 SIP Deskphone	7.1.2.0.14
Avaya J179 H323 Deskphone	6.7.002U
Avaya J129 SIP Deskphone	1.0.0.0.0.43
Avaya Equinox running on Vantage	3.4.8.36
Avaya 9408 Digital Deskphone	V2.0
Ascom Equipment	Software / Firmware Version
Ascom Device Manager running on Unite Connectivity Manager	5.11.2
Ascom WinPDM running on Windows 7 PC	3.11.1
Ascom i62 VoWiFi Handset	6.2.0
Ascom approved Wi-Fi Access Point	Ascom approved software version

5. Configure Avaya Aura® Communication Manager

It is assumed that a fully functioning Communication Manager is in place with the necessary licensing with SIP trunks in place to Session Manager. For further information on the configuration of Communication Manager please see **Section Error! Reference source not found.** of these Application Notes.

Note: A printout of the Signalling and Trunk groups that were used during compliance testing can be found in the **Appendix** of these Application Notes.

The following sections go through the following.

- System Parameters
- Dial Plan Analysis
- Feature Access Codes
- Network Region
- IP Codec
- Coverage Path/Hunt Group

5.1. Configure System Parameters

Ensure that the SIP endpoints license is valid as shown below by using the command **display system-parameters customer-options**.

```
display system-parameters customer-options                               Page 1 of 12
                                OPTIONAL FEATURES

G3 Version: V17                                                         Software Package: Enterprise
Location: 2                                                             System ID (SID): 1
Platform: 28                                                            Module ID (MID): 1

                                USED
Platform Maximum Ports: 48000 168
Maximum Stations: 36000 44
Maximum XMOBILE Stations: 36000 0
Maximum Off-PBX Telephones - EC500: 41000 2
Maximum Off-PBX Telephones - OPS: 41000 20
Maximum Off-PBX Telephones - PBFMC: 41000 0
Maximum Off-PBX Telephones - PVFMC: 41000 0
Maximum Off-PBX Telephones - SCCAN: 0 0
Maximum Survivable Processors: 313 1
```


5.2. Configure Dial Plan Analysis

Use the **change dialplan analysis** command to configure the dial plan using the parameters shown below. Extension numbers (**ext**) are those beginning with **21**. Feature Access Codes (**fac**) use digits **8** and **9** and use characters ***** or **#**.

```

change dialplan analysis                                     Page 1 of 12
                                                           DIAL PLAN ANALYSIS TABLE
                                                           Location: all                                     Percent Full: 5

```

Dialed String	Total Length	Call Type	Dialed String	Total Length	Call Type	Dialed String	Total Length	Call Type
21	4	ext						
3	4	udp						
8	1	fac						
9	1	fac						
*8	4	dac						
*	3	fac						
#	3	fac						

5.3. Configure Feature Access Codes

Use the **change feature-access-codes** command to configure access codes which can be entered from i62 handsets to initiate Communication Manager Call features. These access codes must be compatible with the dial plan described in **Section 5.2**. Some of the access codes configured during compliance testing are shown below.

```

change feature-access-codes                               Page 1 of 12
                                                           FEATURE ACCESS CODE (FAC)

```

Abbreviated Dialing List1 Access Code:	*11	
Abbreviated Dialing List2 Access Code:	*12	
Abbreviated Dialing List3 Access Code:	*13	
Abbreviated Dial - Prgm Group List Access Code:	*10	
Announcement Access Code:	*27	
Answer Back Access Code:	#02	
Attendant Access Code:		
Auto Alternate Routing (AAR) Access Code:	8	
Auto Route Selection (ARS) - Access Code 1:	9	Access Code 2:
Automatic Callback Activation:	*05	Deactivation: #05
Call Forwarding Activation Busy/DA:	*03 All: *04	Deactivation: #04
Call Forwarding Enhanced Status:	*73 Act: *74	Deactivation: #74
Call Park Access Code:	*02	
Call Pickup Access Code:	*09	
CAS Remote Hold/Answer Hold-Unhold Access Code:		
CDR Account Code Access Code:	*14	
Change COR Access Code:		
Change Coverage Access Code:		
Conditional Call Extend Activation:		Deactivation:
Contact Closure Open Code:		Close Code:

5.4. Configure Network Region

Use **change ip-network-region x** (where x is the network region to be configured) to assign an appropriate domain name to be used by Communication Manager, in the example below **devconnect.local** is used. Note that this domain is also configured in **Section 6.1.1**.

```
change ip-network-region 1                               Page 1 of 20
                                                    IP NETWORK REGION
  Region: 1          NR Group: 1
Location: 1          Authoritative Domain: devconnect.local
  Name: PG Default   Stub Network Region: n
MEDIA PARAMETERS    Intra-region IP-IP Direct Audio: yes
  Codec Set: 1       Inter-region IP-IP Direct Audio: yes
  UDP Port Min: 2048 IP Audio Hairpinning? n
  UDP Port Max: 3329
DIFFSERV/TOS PARAMETERS
  Call Control PHB Value: 46
    Audio PHB Value: 46
    Video PHB Value: 26
802.1P/Q PARAMETERS
  Call Control 802.1p Priority: 6
    Audio 802.1p Priority: 6
    Video 802.1p Priority: 5
AUDIO RESOURCE RESERVATION PARAMETERS
H.323 IP ENDPOINTS  RSVP Enabled? n
  H.323 Link Bounce Recovery? y
  Idle Traffic Interval (sec): 20
  Keep-Alive Interval (sec): 5
```

5.5. Configure IP-Codec

Use the **change ip-codec-set x** (where x is the ip-codec set used) command to designate a codec set compatible with the i62 Handsets. During compliance testing the codecs **G.711A**, **G.729A** and **G.722-64K** were tested.

```
change ip-codec-set 1                               Page 1 of 2
                                                    IP MEDIA PARAMETERS
  Codec Set: 1
Audio      Silence   Frames   Packet
Codec      Suppression Per Pkt   Size(ms)
1: G.711A          n         2        20
2: G.729A          n         2        20
3: G.722.2      n         1        20
4: G.722-64K       2         2        20
5: G.723-5.3K  n         1        30
6:
7:
Media Encryption      Encrypted SRTCP: enforce-unenc-srtcp
1: 1-srtp-aescm128-hmac80
2: none
3:
4:
```

5.6. Configuration of Coverage Path and Hunt Group for voicemail

The coverage path setup used for compliance testing is illustrated below. Note the following:

Don't Answer is set to **y**: The coverage path will be used in the event the phone set is not answered.

Number of Rings is set to **4**: The coverage path will be used after 4 rings.

Point 1 is set to **h6**: Hunt Group 6 is utilised by this coverage path.

```

display coverage path 1
                                COVERAGE PATH

                                Coverage Path Number: 1
                                Cvg Enabled for VDN Route-To Party? n      Hunt after Coverage? n
                                Next Path Number:                          Linkage

COVERAGE CRITERIA
  Station/Group Status   Inside Call   Outside Call
    Active?               n             n
    Busy?                  Y             Y
    Don't Answer?       Y           Y           Number of Rings: 4
    All?                   n             n
  DND/SAC/Goto Cover?   Y             Y
  Holiday Coverage?     n             n

COVERAGE POINTS
  Terminate to Coverage Pts. with Bridged Appearances? n
  Point1: h6           Rng:         Point2:
  Point3:                 Point4:
  Point5:                 Point6:
  
```

The hunt group used for compliance testing is shown below. Note that on **Page 1** the **Group Extension** is **6666**, which is used to dial for messaging and **Group Type** is set to **ucd-mia**.

```

display hunt-group 6
                                HUNT GROUP
                                Page 1 of 60

                                Group Number: 6                          ACD? n
                                Group Name: AA Messaging V7                    Queue? n
                                Group Extension: 6666                          Vector? n
                                Group Type: ucd-mia                            Coverage Path: 1
                                TN: 1                                         Night Service Destination:
                                COR: 1                                         MM Early Answer? n
                                Security Code:                                  Local Agent Preference? n
                                ISDN/SIP Caller Display: mbr-name


SIP URI::
  
```

On **Page 2** Message Center is set to **sip-adjunct**.


display hunt-group 6		Page 2 of 60	
HUNT GROUP			
Message Center: sip-adjunct			
Voice Mail Number	Voice Mail Handle	Routing Digits (e.g., AAR/ARS Access Code)	
6666	6666	9	

6. Configure Avaya Aura® Session Manager

The Ascom i62 VoWiFi handsets are added to Session Manager as SIP users. To make changes on Session Manager a web session is established to System Manager. Log into System Manager by opening a web browser and navigating to <https://<System Manager FQDN>/SMGR>. Enter the appropriate credentials for the **User ID** and **Password** and click on **Log On**.



Once logged in navigate to **Elements** and click on **Routing** highlighted below.




6.1. Domains and Locations

Note: It is assumed that a domain and a location have already been configured, therefore a quick overview of the domain and location that was used in compliance testing is provided here.

6.1.1. Display the Domain

Select **Domains** from the left window. This will display the domain configured on Session Manager. For compliance testing this domain was **devconnect.local** as shown below. If a domain is not already in place, click on **New**. This will open a new window (not shown) where the domain can be added.




The screenshot shows the Avaya Aura System Manager 8.0 interface. The top navigation bar includes 'Users', 'Elements', 'Services', 'Widgets', and 'Shortcuts'. The left sidebar is expanded to 'Routing', and 'Domains' is selected. The main content area is titled 'Domain Management' and features a table with one item:

Name	Type	Notes
devconnect.local	sip	devconnect.local

Buttons for 'New', 'Edit', 'Delete', 'Duplicate', and 'More Actions' are visible above the table. A 'Select : All, None' option is at the bottom of the table.

6.1.2. Display the Location

Select **Locations** from the left window and this will display the location setup. The example below shows the location **DevConnectLab_PG** which was used for compliance testing. If a location is not already in place, then one must be added to include the IP address range of the Avaya solution. Click on **New** to add a new location.




The screenshot shows the Avaya Aura System Manager 8.0 interface. The top navigation bar includes 'Users', 'Elements', 'Services', 'Widgets', and 'Shortcuts'. The left sidebar is expanded to 'Routing', and 'Locations' is selected. The main content area is titled 'Location' and features a table with one item:

Name	Correlation	Notes
DevConnectLab_PG	<input type="checkbox"/>	DevConnectLab_PG


Buttons for 'New', 'Edit', 'Delete', 'Duplicate', and 'More Actions' are visible above the table. A 'Select : All, None' option is at the bottom of the table.

6.2. Adding Ascom SIP Users

From the home page, click on **User Management** → **Manager Users** shown below.



From **Manager Users** section, click on **New** to add a new SIP user.



Under the **Identity** tab fill in the user’s desired **Last Name** and **First Name** as shown below. Enter the **Login Name** following the format of “user id@domain”. The remaining fields can be left as default.

The screenshot shows the 'User Profile | Edit | 2154@devconnect.local' interface. The 'Identity' tab is selected. The form includes the following fields:


- User Provisioning Rule: [Dropdown]
- * Last Name: [Text: Ascom]
- * First Name: [Text: i62_2154]
- * Login Name: [Text: 2154@devconnect.local]
- Description: [Text: Description Of User]
- Password: [Text:]
- Confirm Password: [Text:]
- Endpoint Display Name: [Text: Ascom, i62_2154]
- Language Preference: [Dropdown: English (United States)]
- Employee ID: [Text: Employee Id Of User]
- Last Name (Latin Translation): [Text: Ascom]
- First Name (Latin Translation): [Text: i62_2154]
- Middle Name: [Text: Middle Name Of User]
- Email Address: [Text: Email Address Of User]
- User Type: [Dropdown: Basic]
- Localized Display Name: [Text: Ascom, i62_2154]
- Title Of User: [Text: Title Of User]
- Time Zone: [Dropdown]
- Department: [Text: Department Of User]

Under the **Communication Profile** tab enter **Communication Profile Password** and **Confirm Password**, note that this password is required when configuring the i62 handset in **Section 7.1**.

The screenshot shows the 'User Profile | Edit | 2150@devconnect.local' interface. The 'Communication Profile' tab is selected. A modal dialog titled 'Comm-Profile Password' is open, containing the following fields:

- Comm-Profile Password: [Text:]
- Re-enter Comm-Profile Password: [Text:]
- Generate Comm-Profile Password: [Link]
- Buttons: Cancel, OK

Staying on the **Communication Profile** tab, click on **New** to add a new **Communication Address**.



Enter the extension number and the domain for the **Fully Qualified Address** and click on **OK** once finished.

The screenshot shows a dialog box titled "Communication Address Add/Edit". It has a close button (X) in the top right corner. The form contains two main fields: "* Type:" with a dropdown menu showing "Avaya SIP", and "*Fully Qualified Address:" which is split into two input boxes: the first contains "2154" and the second contains "devconnect.local" with an "@" symbol between them. At the bottom right, there are two buttons: "Cancel" and "OK".

Ensure **Session Manager Profile** is checked and enter the **Primary Session Manager** details, enter the **Origination Sequence** and the **Termination Sequence**. Scroll down to complete the profile.

Identity	Communication Profile	Membership	Contacts
Communication Profile Password			
PROFILE SET: Primary ▼			
Communication Address			
PROFILES			
Session Manager Profile <input checked="" type="checkbox"/>			
CM Endpoint Profile <input checked="" type="checkbox"/>			
SIP Registration			
* Primary Session Manager: SM80vmpg <input type="text"/> <input type="button" value="Q"/> <input type="button" value="i"/>			
Secondary Session Manager: Start typing... <input type="text"/> <input type="button" value="Q"/> <input type="button" value="i"/>			
Survivability Server: Start typing... <input type="text"/> <input type="button" value="Q"/> <input type="button" value="i"/>			
Max. Simultaneous Devices: 1 <input type="text"/>			
Block New Registration When <input type="checkbox"/>			
Maximum Registrations			
Active? *			
Application Sequences			
Origination Sequence: CMAPPSEQ <input type="text"/>			
Termination Sequence: CMAPPSEQ <input type="text"/>			

Enter the **Home Location**, this should be the location configured in **Section 6.1.2**. Click on Commit at the top of the page (not shown).

Application Sequences

Origination Sequence:

Termination Sequence:

Emergency Calling Application Sequences

Emergency Calling Origination Sequence:

Emergency Calling Termination Sequence:

Call Routing Settings

* Home Location:

Conference Factory Set:

Call History Settings

Enable Centralized Call History?

Ensure that **CM Endpoint Profile** is selected in the left window. Select the Communication Manager that is configured for the **System** and choose the **9620SIP_DEFAULT_CM_8_0** as the **Template**. Enter the appropriate **Voice Mail Number** and **Sip Trunk** should be set to **aar**, providing that the routing is setup correctly on Communication Manager. The **Profile Type** should be set to **Endpoint** and the **Extension** is the number assigned to the i62 handset. Click on **Endpoint Editor** to configure the buttons and features for that handset on Communication Manager.

The screenshot shows the 'User Profile | Edit | 2154@devconnect.local' interface. The 'Communication Profile' tab is active. The left sidebar shows 'CM Endpoint Profile' selected. The main configuration area includes the following fields and options:

- System:** CM80vmpg
- Profile Type:** Endpoint
- Use Existing Endpoints:**
- Extension:** 2154
- Template:** 9620SIP_DEFAULT_CM_8_0
- Set Type:** 9620SIP
- Sub Type:** Select
- Terminal Number:** 0 0 0 0
- System ID:** Enter System Id
- Security Code:** Enter Security Code
- Port:** IP
- Voice Mail Number:** 6666
- Preferred Handle:** Select
- Calculate Route Pattern:**
- Sip Trunk:** aar
- SIP URI:** Select
- Enhanced Callr-Info display for 1-line phones:**
- Delete on Unassign from User or on Delete User:**
- Override Endpoint Name and Localized Name:**
- Allow H.323 and SIP Endpoint Dual Registration:**


Under the **General Options** tab ensure that **Coverage Path 1** is set to that configured in **Section 5.6**. Also ensure that **Message Lamp Ext.** is showing the correct extension number. The **Class of Restriction** and **Class of Service** should be set to the appropriate values for the i62 handset. This may vary depending on what level of access/permissions the handset has been given. Other tabs can be checked but for compliance testing the values were left as default. Click on Done (not shown) to complete.

Note: For compliance testing the default value of three call appearance buttons were used. This can be changed under the **Button Assignment** tab.

Once the **CM Endpoint Profile** is completed correctly, click on **Commit** to save the new user.

7. Configure Ascom i62 VoWiFi Handsets

The configuration of the i62 handsets is done using Ascom's WinPDM software installed on a PC. Attach the Ascom DeskTop Programmer DP1 USB cradle to a PC on which the Ascom WinPDM has been installed. Insert the handset to be configured in the DP1 USB Cradle, start the Ascom Device Manager, select the **Numbers** tab and click **New** icon highlighted below.




Place a new i62 to be programmed into the cradle and the following screen should appear automatically. Select **Edit parameters** and click on **Next** as shown below.



7.1. Configure SIP settings

Select **VoIP** → **General** from the left window. In the main window ensure the following are set.


- **Replace Call Rejected with User Busy:** **Yes**
- **VoIP Protocol:** **SIP**
- **Codec configuration:** **G.711A-law** (as desired based on **Section 5.5**)
- **Codec packetization time configuration:** **20** (as configured in **Section 5.5**)
- **Internal call number length:** **4** (matches #digits in Endpoint number)
- **Endpoint number:** User extension from **Section 6.2.**
- **Endpoint ID:** Can be left blank



Select the **VoIP→SIP** menu point, and enter the values shown below.

- **Primary SIP proxy:** IP address of Session Manager’s signaling interface.
- **Listening port:** **5060**
- **SIP proxy password:** Password assigned to the endpoint in **Section 6.2**.
- **Registration identity:** Enter **Endpoint number**.
- **Authentication identity:** Enter **Endpoint number**
- **SIP Register Expiration:** **120** (recommended value)
- **Direct Signaling** This was left as **No** for compliance testing
- **Disable PRACK** This was set to **Yes** for compliance testing


Direct Signaling defines whether calls can be redirected to or accepted from other sources than the configured SIP Proxy. Retain default values for all other fields.



For further information about the Ascom i62 handset configurations please refer to Ascom’s documentation in **Section 10** of these Application Notes. This section only covers specific settings concerning SIP.

7.2. Configure Message Centre


Click on **Device** → **Message centre** in the left window. In the right window, enter the **Voice mail number** as configured in **Section 5.6** and the **Message Centre number** which is the extension number of the handset. Message waiting on/off comes from SIP messages originating from Avaya Aura® Messaging so there is no call to set this value on the Ascom phone.




7.3. Configure Multi-Device Access

The MDA feature allows users to leverage multiple devices (endpoints) simultaneously to meet their communication needs. Users can send and receive calls at multiple devices and move calls between devices as needed.


For i62 handset, the MDA feature can be accomplished by configuring and registering the handset using the Endpoint ID parameter. In the example below, handset device with extension number 2157 is configured to register as user 2154. As shown in the screen below, **Endpoint number** is configured as **2157** however **Endpoint ID** is configured as **2154**. As per design, the Endpoint number needs to be unique while configuring the i62 handset via WinPDM.



Also, the **Registration identity** and **Authentication identity** are both configured as **Endpoint number** as shown below.



For the **Message Centre number** instead of the extension number of the handset, configure the Endpoint ID which is **2154** in this case.



8. Verification Steps

The following steps can be taken to ensure that connections between Ascom i62 handsets and Session Manager and Communication Manager are up.

8.1. Session Manager Registration

Log into System Manager as done previously in **Section Error! Reference source not found.**, select **Session Manager** → **Dashboard**.

The screenshot displays the Avaya Aura System Manager 8.0 dashboard. The top navigation bar includes 'Users', 'Elements', 'Services', 'Widgets', and 'Shortcuts'. The main content area is divided into several sections:

- System Resource Utilization:** A bar chart showing resource usage for 'opt', 'var', and 'emdata' categories. The y-axis ranges from 0 to 28.
- Alarms:** A section with a legend for Critical (red), Major (orange), Indeterminate (blue), Minor (yellow), and Warning (purple). A large yellow circle is visible, indicating a warning or minor alarm.
- Application State:** A table showing the status of various components:

License Status	Active
Deployment Type	VMware
Multi-Tenancy	DISABLED
OOBM State	DISABLED
Hardening Mode	Standard
- Information:** A table showing the count and sync status of elements:

Elements	Count	Sync Status
CM	1	■
Session Manager	1	■
System Manager	1	■
UCM Applications	8	■


A navigation menu is open, showing the following options:

- Avaya Breeze®
- Communication Manager
- Communication Server 1000
- Conferencing
- Device Adapter
- Device Services
- Media Server
- Meeting Exchange
- Messaging
- Presence
- Routing
- Session Manager
- Web Gateway

The Session Manager section is expanded, showing a sub-menu with the following options:

- Dashboard
- Session Manager Administration
- Global Settings
- Communication Profile Editor
- Network Configuration
- Device and Location Configuration
- Application Configuration

Under **System Status** in the left window, select **User Registrations** to display all the SIP users that are currently registered with Session Manager.



The i62 users should show as being registered as shown below.

	Details	Address	First Name	Last Name	Actual Location	IP Address	Remote Office	Shared Control	Simult. Devices	AST Device	Registered		
											Prim	Sec	Surv
<input type="checkbox"/>	Show	2105@devconnect.local	Equinox SIP	Ext2105	DevConnectLab_PG	10.10.40.240	<input type="checkbox"/>	<input type="checkbox"/>	1/1	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> (AC)	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Show	2103@devconnect.local	Equinox SIP	Ext2103	DevConnectLab_PG	10.10.40.236	<input type="checkbox"/>	<input type="checkbox"/>	1/1	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> (AC)	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Show	2154@devconnect.local	i62_2154	Ascom	DevConnectLab_PG	10.10.40.201	<input type="checkbox"/>	<input type="checkbox"/>	1/3	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Show	2109@devconnect.local	3129	Ext2109	DevConnectLab_PG	10.10.40.194	<input type="checkbox"/>	<input type="checkbox"/>	1/1	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> (AC)	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Show	2160@devconnect.local	MYCO2160	Ascom	DevConnectLab_PG	10.10.40.186	<input type="checkbox"/>	<input type="checkbox"/>	1/1	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Show	2150@devconnect.local	DECT2150	Ascom	DevConnectLab_PG	10.10.40.128	<input type="checkbox"/>	<input type="checkbox"/>	1/1	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Show	...	i62_2155	Ascom	<input type="checkbox"/>	<input type="checkbox"/>	0/1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Show	...	MYCO2161	Ascom	<input type="checkbox"/>	<input type="checkbox"/>	0/1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Show	...	SIP	Ext2101	<input type="checkbox"/>	<input type="checkbox"/>	0/1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Show	...	i62_2157	Ascom	<input type="checkbox"/>	<input type="checkbox"/>	0/1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Show	...	DECT2151	Ascom	<input type="checkbox"/>	<input type="checkbox"/>	0/1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Show	...	i62_2156	Ascom	<input type="checkbox"/>	<input type="checkbox"/>	0/1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Show	...	SIP	Ext2100	<input type="checkbox"/>	<input type="checkbox"/>	0/1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Show	...	MYCO2159	Ascom	<input type="checkbox"/>	<input type="checkbox"/>	0/3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

The Ascom i62 user **2154** should show as being registered as shown below. It has an **IP Address** associated with it and there is a tick in the **Registered Prim** box.

User Registrations							
Select rows to send notifications to devices. Click on Details column for complete registration status.							
View ▾		Default		Export		Force Unregister	
				AST Device Notifications:		Reboot	
				Reload ▾		Failback	
19 Items		Show		15 ▾			
<input type="checkbox"/>	Details	Address	First Name	Last Name	Actual Location	IP Address ▾	Remote Office
<input type="checkbox"/>	▶ Show	2105@devconnect.local	Equinox SIP	Ext2105	DevConnectLab_PG	10.10.40.240	<input type="checkbox"/>
<input type="checkbox"/>	▶ Show	2103@devconnect.local	Equinox SIP	Ext2103	DevConnectLab_PG	10.10.40.236	<input type="checkbox"/>
<input type="checkbox"/>	▶ Show	2154@devconnect.local	i62_2154	Ascom	DevConnectLab_PG	10.10.40.201	<input checked="" type="checkbox"/>
<input type="checkbox"/>	▶ Show	2109@devconnect.local	J129	Ext2109	DevConnectLab_PG	10.10.40.194	<input type="checkbox"/>
<input type="checkbox"/>	▶ Show	2160@devconnect.local	MYCO2160	Ascom	DevConnectLab_PG	10.10.40.186	<input type="checkbox"/>
<input type="checkbox"/>	▶ Show	2150@devconnect.local	DECT2150	Ascom	DevConnectLab_PG	10.10.40.128	<input type="checkbox"/>

8.2. Ascom i62 Registration

The Ascom i62 handset connection to Session Manager can be verified by an absence of an error message on the handset display just above the red line at the bottom of the display, as shown in the following illustration, (note this is an example from compliance testing).



9. Conclusion

These Application Notes describe the configuration steps required for Ascom's i62 VoWiFi handsets to successfully interoperate with Avaya Aura® Communication Manager R8.0.1 and Avaya Aura® Session Manager R8.0.1 by registering the Ascom i62 handsets with Avaya Aura® Session Manager as SIP users. Please refer to **Section 2.2** for test results and observations.

10. Additional References

This section references the product documentation relevant to these Application Notes.

Product documentation for Avaya products may be found at <http://support.avaya.com>.

1. *Deploying Avaya Aura® Communication Manager*, Release 8.0
2. *Avaya Aura® Communication Manager Feature Description and Implementation*, Release 8.0
3. *Deploying Avaya Aura® Session Manager*, Release 8.0
4. *Administering Avaya Aura® Session Manager*, Release 8.0
5. *Deploying Avaya Aura® System Manager*, Release 8.0
6. *Administering Avaya Aura® System Manager for Release 8.0*, Release 8.0
7. *Deploying Avaya Aura® Messaging using VMware® in the Virtualized Environment*, Release 7.0.0
8. *Administering Avaya Aura® Messaging*, Release 7.0.0

Documentation for Ascom products can be obtained from an Ascom supplier or may be accessed at <https://www.ascom-ws.com/AscomPartnerWeb/Templates/WebLogin.aspx> (login account for the Ascom Partner Extranet required).

Appendix

Signaling Group

```
display signaling-group 1                               Page 1 of 3
                SIGNALING GROUP

Group Number: 1                Group Type: sip
IMS Enabled? n                Transport Method: tls
    Q-SIP? n
    IP Video? n                Enforce SIPS URI for SRTP? n
Peer Detection Enabled? y Peer Server: SM                Clustered? n
Prepend '+' to Outgoing Calling/Alerting/Diverting/Connected Public Numbers? y
Remove '+' from Incoming Called/Calling/Alerting/Diverting/Connected Numbers? n
Alert Incoming SIP Crisis Calls? n
    Near-end Node Name: procr                Far-end Node Name: SM80vmpg
    Near-end Listen Port: 5061                Far-end Listen Port: 5061
                Far-end Network Region: 1

Far-end Domain:

Incoming Dialog Loopbacks: eliminate                Bypass If IP Threshold Exceeded? n
    DTMF over IP: rtp-payload                RFC 3389 Comfort Noise? n
Session Establishment Timer(min): 3                Direct IP-IP Audio Connections? y
    Enable Layer 3 Test? y                IP Audio Hairpinning? n
H.323 Station Outgoing Direct Media? n                Initial IP-IP Direct Media? n
                Alternate Route Timer(sec): 6
```

Trunk Group Page 1

```
display trunk-group 1                               Page 1 of 5
                TRUNK GROUP

Group Number: 1                Group Type: sip                CDR Reports: y
    Group Name: SIPTRUNK-SM80                COR: 1                TN: 1                TAC: *801
    Direction: two-way                Outgoing Display? n
    Dial Access? n                Night Service:
Queue Length: 0
Service Type: tie                Auth Code? n
                Member Assignment Method: auto
                Signaling Group: 1
                Number of Members: 10
```

Page 2

```
display trunk-group 1                                     Page 2 of 5
  Group Type: sip

TRUNK PARAMETERS

  Unicode Name: auto

                                     Redirect On OPTIM Failure: 5000

  SCCAN? n                                     Digital Loss Group: 18
                                     Preferred Minimum Session Refresh Interval(sec): 600

Disconnect Supervision - In? y Out? y

  XOIP Treatment: auto   Delay Call Setup When Accessed Via IGAR? n

Caller ID for Service Link Call to H.323 1xC: station-extension
```

Page 3

```
display trunk-group 1                                     Page 3 of 5
TRUNK FEATURES
  ACA Assignment? n                                     Measured: none
                                                         Maintenance Tests? y

  Suppress # Outpulsing? n   Numbering Format: private
                                     UII Treatment: shared
                                     Maximum Size of UII Contents: 128
                                     Replace Restricted Numbers? n
                                     Replace Unavailable Numbers? n

                                     Hold/Unhold Notifications? y
  Send UCID? y                                     Modify Tandem Calling Number: no

  Show ANSWERED BY on Display? y

  DSN Term? n
```


Page 4

```
display trunk-group 1                                     Page 4 of 5
                SHARED UI FEATURE PRIORITIES

                ASAI: 1

                Universal Call ID (UCID): 2

MULTI SITE ROUTING (MSR)

                In-VDN Time: 3
                VDN Name: 4
                Collected Digits: 5
                Other LAI Information: 6
                Held Call UCID: 7
```

Page 5

```
trunk-group 1                                           Page 5 of 5
                PROTOCOL VARIATIONS

                Mark Users as Phone? n
Prepend '+' to Calling/Alerting/Diverting/Connected Number? n
                Send Transferring Party Information? y
                Network Call Redirection? y
                Build Refer-To URI of REFER From Contact For NCR? n
                Send Diversion Header? n
                Support Request History? y
                Telephone Event Payload Type: 101

                Convert 180 to 183 for Early Media? n
                Always Use re-INVITE for Display Updates? n
                Identity for Calling Party Display: P-Asserted-Identity
                Block Sending Calling Party Location in INVITE? n
                Accept Redirect to Blank User Destination? n
                Enable Q-SIP? n

                Interworking of ISDN Clearing with In-Band Tones: keep-channel-active
                Request URI Contents: may-have-extra-digits
```

©2019 Avaya Inc. All Rights Reserved.

Avaya and the Avaya Logo are trademarks of Avaya Inc. All trademarks identified by ® and ™ are registered trademarks or trademarks, respectively, of Avaya Inc. All other trademarks are the property of their respective owners. The information provided in these Application Notes is subject to change without notice. The configurations, technical data, and recommendations provided in these Application Notes are believed to be accurate and dependable, but are presented without express or implied warranty. Users are responsible for their application of any products specified in these Application Notes.

Please e-mail any questions or comments pertaining to these Application Notes along with the full title name and filename, located in the lower right corner, directly to the Avaya DevConnect Program at devconnect@avaya.com.